

## **TEST REPORT**

5001 East Philadelphia Street Ontario, California – USA 91761-2816

Ph: 909.472.4100 | Fax: 909.472.4243 http://www.iapmortl.org

Report Number:	2505-18005				
Report Issued:	December 19, 2018	Project No.: 31424			
Client:	DALDORADO				
	4327 Arnold Ave				
	Naples FL, 54104				
	Contact: Ray Vaughn				
Source of Samples:	rce of Samples: The unit was shipped to IAPMO R&T Lab from Daldorado and was received				
	prototype on December 14, 2018				
Location of Testing:	lampo R&T Lab, 5001 East Philadelphia Street, Ontario CA 91761				
Datas of Evoluation	December 17 <sup>th</sup> December 10 <sup>th</sup> 2018				
Dates of Evaluation:	December 17 - December 19 2018				
Product Description:	Current Flow Fitting Wall 300 gpm with $4^{\prime\prime}$ pipe connection for the inlet and 2				
	slits (10"x0.25"each) for the outlet.				
Primary Standard:	Manufacturer scope of work				
Scone of Evaluation:	Elow testing at 200, 250 and 400 gpm, proceure drop across f	itting face and			
	velocity calculation.				
Conclusion:	the scope of evaluation. Please refer to the following pages	s for details.			
	,				
Report Status:	COMPLETE				

Tested By,

Histanto

Reviewed By,

Aul-

Victor Soria, Test

Sal Aridi - Director

## **Test Setup:**

The sample was placed in a tank and connected to a 4" Schd 40 PVC pipe to a pump and flowmeter. A tap was placed in the center side of the sample and connected to a pressure gage placed 29 inches above the tap. The water level was 14.125 inches above the tap. (see Figure 1).

## Data:

				Water Velocity
Flow Rate	Inlet	Outlet pressure	Net Pressure Drop	Through Each Slit $^*$
(gpm)	Pressure (psi)	(psi)	(psi)	(ft/sec)
300	3.6	0.5	3.1	19.25
350	4.4	0.5	3.9	22.46
400	5.5	0.5	5.0	25.67

Table 1- Pressure Drop And Speed Data

<sup>\*</sup>The velocity is based on calculating the flow rate through the area of the 2 slits.

## Figure 1- Sample setup









